

Arizona Mine Reclamation L.L.C.



Level 2V

Vertical Shaft

3/8" Material, Concrete Footer

Level 2 protection is classified as the highest level of re-enterable security to an open air and wildlife design in shaft and adit form. Level 2 protection offers Arizona Mine Reclamation L.L.C. exclusive hidden lock design. In this design the lock is not considered the weak link in the overall structure. This level of protection does require utilizing Arizona Mine Reclamation L.L.C. for re-entry into the site if and when needed by the correct state or federal agency.

Construction of shaft (cupola) will consist of rounded corner steel posts in 12 x 12 x 3/8 inch form set minimum 3 feet in substrate and anchored with concrete (not to exceed 8 feet between posts – additional posts as needed). The corner posts are concrete poured and steel capped. Side Rails are 4" x 4" x 3/8" angle iron set at a minimum open of 5 3/4 inches to a maximum 8 inches apart on horizontal opening and incorporating 2 – 1 1/2 " stiffeners welded to the inside of the 90 degree angle iron horizontals. Top will consist of the same design and requirements as horizontals with the addition of end caps welded to prevent entry or prying between header beam and top mounted angle iron (rails). Finished top rails and caps are to be flush with the header support rail (no protrusion). All side rails to be evenly spaced as required starting at the top and working down to bottom rail or sill. Overall construction dimensions will take into account a size to allow the top rails to be placed and evenly spaced at the required spacing so as not to create a smaller or larger than acceptable opening in top rails as determined in the overall design. In addition the work will consist of installing a 2-3 foot deep and 2 feet thick footer between corner posts to aid in leveling sill plate and prevent tunneling access. When required additional 2-3 foot x 5/8" steel pinning may be placed in footer trench to thereby add an additional depth of protection. Steel pins will extend thru concrete footer to aid in bottom sill plate placement (welding). An additional top sill plate or angle iron is welded to the bottom sill plate to protect pin welds.

- See Accompanying **Level 2V** - Vertical Shaft Draft •

Arizona Mine Reclamation L.L.C.



Level 2HA

Horizontal or Adit

3/8" Material, Concrete Footer

Level 2 protection is classified as the highest level of re-enterable security to an open air and wildlife design in shaft and adit form. Level 2 protection offers Arizona Mine Reclamation L.L.C. exclusive hidden lock design. In this design the lock is not considered the weak link in the overall structure. This level of protection does require utilizing Arizona Mine Reclamation L.L.C. for re-entry into the site if and when needed by the correct state or federal agency.

- Construction will consist of verticals utilizes minimum 1" thick 4" wide verticals to maximum 8" x 8" x 3/8" rounded steel posts set in floor and anchored at roof utilizing minimum 16" length and 5/8" diameter steel pins set and anchored to verticals on closed off side of mine with a welded anchor plate and gusset 3/8" thickness to prevent access to steel pins (minimum 1 steel pin for every 8 inches of anchor plate).
- Floor will utilize minimum 2' x 2' concrete footer, pinned for sill attachment
- All Pins epoxy or concrete set.
- Horizontal rail will consist of 4" x 4" x 3/8" angle iron with 2-1 1/2" stiffeners welded in place to mid-line vertical supports at a minimum spacing of 5 3/4" to a maximum of 8" spacing as requested. Horizontal spacing will start at top and be spaced evenly down to floor with any odd measurement of offset spacing being at floor level so as to utilize as much of the adit opening as possible for wildlife access.

- See Accompanying **Level 2HA** Horizontal or Adit Draft